melamine to the ends.

Written by Hans Summers Sunday, 05 April 2009 15:14 - Last Updated Sunday, 19 April 2009 08:05

The G0UPL workbench is built entirely from materials from UK DIY store  $\frac{\text{Homebase}}{\text{Homebase}}$ . The workbench area is 8 x 3 feet, with two shelves 8 feet x 9 inches, constructed from 15mm thickness melamine (white coated MDF). A total of 216 screws were used in the construction. The following photographs show stages of construction. Click for larger versions.

The following photographs show stages of construction. Click for larger versions.
{gallery}workbench{/gallery}
Image details:
1: <b>Raw materials:</b> 8-foot melamine planks, 6-foot spruce planks, six steel table legs, two steel tubes (clothes rails), assorted screws and fittings.
2: <b>Simple tools:</b> Hacksaw, <u>Poundland</u> screwdrivers, <u>Poundland</u> tape measure, <u>PSU</u> , Miniature drill
3: <b>Worktop construction:</b> First step in the construction: to screw three 8 x 1 foot Melamine planks together using 30-inch spruce planks. The six steel table legs are screwed to the spruce planks.
4: <b>Table leg:</b> Close-up showing one of the <u>Homebase</u> table legs screwed to the worktop.
5: Workbench top: Now it starts to look like a real table, after carefully turning over.
6: <b>Shelves:</b> The shelves are constructed from 8 foot x 9 inch Melamine, supported using 25cm steel tubes cut from clothes rail and fixed to the shelves using clothes rail end fittings.
7: Corner support: The shelves are made strong and rigid by screwing on further pieces of

## **G0UPL** workbench

Written by Hans Summers Sunday, 05 April 2009 15:14 - Last Updated Sunday, 19 April 2009 08:05

- 8: **Electrical sockets:** Another view of the shelves, and an opportune moment to mention the 16 mains sockets ( <a href="Poundland">Poundland</a> 4-way extensions).
- 9: **Wiring:** The electrical sockets are switched in banks of 4-4-8 using a triple switch mounted in the centre of the bench, wired on the underside to connection boxes.
- 10: **More support:** Further support to the melamine planks using 15-inch spruce planks screwed under the worktop. Those are my knees bottom right as I'm on my back to take the photo.
- 11: **Finished!** Workbench moved into its final position, with equipment and components loaded onto the shelves.
- 12: **Equipment:** Closer view of workbench: test equipment, tools and components on the left; radio station on the right ( RX, TX, ATU, PSU).